ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Notification dated 3rd August 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2 P.M. on 26th August 1939, for constructing first floor for the Mathematics block, Central College, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1 650 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing first floor for the Mathematics block Central College, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract tender for constructing First Floor for the Mathematics Block, Central College Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Dismantling brick parapet wall	R.ft.	0 0 3	953	
2	Cutting open Madras Terrace roofing	Sqr.	2 0 0	1·40	
3	Removing ventilators of certain hall	Sq.ft	0 1 0	110	
4	Scraping out the surki concrete after removing courses of flat tiles on Madras Terrace roofing ..	Sqr	1 0 0	109·00	
5	Burnt brick in lime mortar for superstructure	C.ft.	0 4 0	19090	
6	Pointed arch work in burnt brick in composite mortar	,,	0 6 0	1184·50	
7	Roofing with R.C.C. (1 : 2 : 4) 2" surki concrete two courses of flat tiles with plastering, etc., for a maximum span of 12'	Sqr.	65 0 0	155·50	
8	Preparing and fixing T. W. door frames 4"×5" 1½" thick shutters ⅓ panelled and ⅔ glazed as per design given with achme brass fittings, etc., complete	Sq.ft.	1 8 0	1.472	
9	Preparing and fixing T. W. windows 4"×5" frame 1½" thick shutters fully glazed with iron bars and achme fittings	,,	1 10 0	768	
10	Preparing and fixing T. W. fanlights frames 4"×5", 1½" thick shutters fully glazed as per design ..	,,	2 8 0	546	
11	Preparing and fixing R.C.C. panels as per approved design	,,	0 12 0	184	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
12	Parapet wall in burnt brick in mortar 1½' high ¾' thick as per approved design with plastering, white washing, colour washing, etc.	R.ft.	0 12 0	953	
13	Flooring with 1½" cement concrete 1 : 2 : 4 mixng with Red Oxide plastering, etc., with cut lines etc., complete	Sqr.	16 0 0	109·00	
14	Plastering in lime mortar	,,	3 0 0	192·50	
15	White washing, two coats	,,	0 3 0	104·60	
16	Colour washing, two coats	,,	0 4 0	88·00	
17	Painting with Government Lac Factory chacolate ..	,,	4 0 0	56·00	
18	Railings as per approved design alround corridor including fixing, etc.	R.ft.	3 0 0	183	
19	Circular columns in wirecut qudrant bricks in compette mortar 14' dia. including base and capital, etc., as per design	C.ft.	0 10 0	890	
20	(a) Supplying and fixing Tata's tested steel girders including hoisting, painting, etc.	C.wt.	12 8 0	305	
	(b) ,, ,, Do built up girders	,,	16 0 0	300	
21	Boxing girders with brick in cement mortar wiring plastering, white washing, etc.	R.ft.	0 10 0	698	
22	Teakwood stairs including fixing, etc., with Newels railings, etc., as per design	Sq.ft.	2 8 0	190	

N.B.—Chamundi Brand Cement must be used.

M. K. RAJAM IYENGAR,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 1st August 1939.

The attention of the public is invited to the Notification calling for tenders for the work of "Giving water supply at Sravanabelagola during the Mahamasthakabhisheka Jatra which will take place at Sravanabelagola during February 1940," published in pages 1522 and 1523, Part VI of the *Mysore Gazette*, dated 3rd August 1939.

The last date of receiving tenders is fixed on 31st August 1939.

N. KRISHNIENGAR,
Sanitary Engineer.

KOLAR DIVISION.

Abstract Notification.

Attention of the public is invited to the further Notification dated 11th July 1939, published on pages 1386-1389 of the *Mysore Gazette*, Part VI, dated 20th July 1939, regarding converting the present District Educational Office building at Kolar, into District Lock-up. Last date for receiving tenders is changed from 14th August 1939 to 21st August 1939.

Abstract Notification 31st July 1939.

The attention of the public is invited to the detailed notification, published on pages 1493-1495, Part VI of the *Mysore Gazette*, dated 3rd August 1939, *re* tenders for the maintenance work to Muduvathi Doddakere Register No. 199/780 of Kolar Taluk (Major Tank).

The last date for receiving tenders is 30th August 1939.

Further Notification, dated 31st July 1939.

The attention of the public is invited to the detailed notification dated 11th July 1939, published on pages 1386-1389, Part VI of the *Mysore Gazette*, dated 20th July 1939. Abstract of estimated quantities for converting the present District Educational Office Buildings at Kolar, into District Lock-up, are published below for the information of the public.

The last date for receiving tenders is changed from 14th August 1939 to 21st August 1939 upto 2 P.M.

Abstract estimate of quantities for converting the present District Educational Offices into District Lock-up at Kolar

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Dismantling brick masonry walls and removing debris	C.ft.	0 0 3	2,933	
2	Removing the existing M. T. roof with rafters and bressummers, etc., complete and stacking the materials	Sqr.	1 4 0	43·32	
3	Dismantling retaining wall including stone slabs and flooring together with levelling the ground	C.ft.	0 0 6	334	
4	Removing doors with shutters and stacking	Each	0 8 0	41	
5	Do do windows	,,	0 4 0	22	
6	Do do ventilators	,,	0 4 0	3	
7	Removing the big door	,,	0 12 0	1	
8	Providing strong doors for lock-up rooms as per type design and estimate	,,	68 0 0	16	
9	Burnt brick in chunam mortar superstructure	C.ft.	0 4 0	4,416	
10	Plastering with chunam mortar 2 coats	Sqr.	2 8 0	54·00	
11	Supplying and fixing T. W. ventilators to lock-up rooms including ¾" dia. iron bars and providing expanded metal, etc., complete with painting	S.ft.	1 8 0	272	
12	Excavating foundation	C.yd.	0 3 0	11	
13	Size stone in clay foundation and basement	C.ft.	0 3 0	304	
14	Re-roofing with pucca terrace brick on edge including chunam plastering on top and bottom and finished as per specifications with necessary slopes using released T. W. rafters	Sqr.	30 0 0	33·23	
15	R. S. beams 12"×5" including hoisting and fixing with prime coat of anti-corrosive paint	Cwt.	12 0 0	9·6	
16	Boxing girders with burnt brick in mortar and plastering	R.ft.	0 8 0	32	
17	Constructing burnt brick in mortar parapet 1¼' high 9" thick plain and finished with plastering as per design	,,	0 12 0	676	
18	Supplying and fixing G. I. rain water down pipes 4" dia. including all fixture	,,	0 6 0	285	
19	Providing plain cornice 6" thick with burnt brick in mortar and plastering including blocking course	Rft.	0 6 0	676	
20	Removing the lean to roof of M. T. and resetting on the other side of room No. 17	L. S.			
21	Constructing a verandah with lean to M. T. roof in front of Lock-up rooms (1 to 15) using released materials	,,			
22	Constructing a B. S. slabbed Latrine and urinal	,,			
	Constructing Kitchen Block.				
1	Excavating foundation and filling in basement including watering and tamping	C.yd.	0 3 0	16	
2	Burnt stone jelly concrete in chunam mortar	C.ft.	0 3 6	80	
3	Burnt size stone in clay foundation and basement	,,	0 3 0	389	
4	Burnt brick in clay superstructure	,,	0 3 3	591	
5	Burnt stone slab 6" thick dressed and fixed	S.ft.	0 4 0	35	
6	Plastering with chunam mortar (2 coats)	Sqr.	2 8 0	13·90	
7	Fixing available doors in the masonry with necessary repairs	Each	1 0 0	3	
8	Do do windows	,,	0 8 0	1	
9	Do do New T. W. ventilators with iron bars, etc., complete	S.ft.	1 8 0	12	
10	Roofing with R. B. C. including plastering at top and bottom and finished as per specification	Sqr.	60 0 0	3.45	
11	Cement pointing to basement including scraping joints ¾" deep	Sqr.	3 14 0	0·53	
12	Constructing parapet with burnt brick in mortar 9" thick and 1' high including plastering, etc., complete	R.ft.	0 12 0	50	
13	Providing G. I. rain water down pipes 4" diameter	,,	0 6 0	36	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
14	Constructing oven, chimney and sinks, etc., complete	L. S.			
15	Constructing bath room with available B. S. slabs	,,			
	Constructing Compound Wall.				
1	Excavating foundation	C.yd.	0 3 0	158	
2	Stone jelly concrete with chunam mortar ..	C.ft.	0 3 6	1,425	
3	Size stone in clay foundation	,,	0 3 0	2,375	
4	Do superstructure	,,	0 3 3	9,619	
5	Cement pointing including scraping joints ¾" deep ..	Sqr.	3 8 0	108·30	
	Providing round coping at top 9" thick including fixing glass pieces in chunam mortar ..	R.ft.	0 4 0	475	
6	Supplying and fixing wrought iron gate as per design to be furnished during execution including painting	L. S.			
7	Repairs to existing doors and windows	L. S.			
8	White and colour washing	Sqr.	0 4 6	400	

C. R. IYENGAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 6th August 1939.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 21st August 1939, for constructing the Kitchen block in P. K. Sanatorium, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing the Kitchen block in P. K. Sanatorium, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 364 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for due fulfilment of the contract. (Cash amount will not carry any interest.) The amount of earnest money should be paid direct to the Treasury and the duplicate Treasury chellan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 21st August 1939 at 4 P.M. The final acceptance of the tender will rest with the Government who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within two months from the date of order for commencing work, failing which the Assistant Engineer may, at his discretion, levy a penalty upto Rs. 50 per day of delay, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery, that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

NOTE.—(*A*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling from excavations and foundations, wherever and whenever necessary, with their own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

NOTE.—(*B*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 4,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore Teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	3	4	0	,,
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	,,
(3) Planks 1″ to 1½″ to required sizes ..	4	8	0	,,

25. Only Chamundi Brand cement should be used for all works requiring this nature.
26. Such of the tenders which do not clearly quote with detailed specification for all the items without exception will not be considered.

Abstract estimate of quantities for constructing kitchen block in P. K. Sanatorium, Mysore.

Sl. No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earth excavation for foundation and filling in basement with watering and consolidation, complete	C.yd.	0 3 6	141	31
2	Do in foundation with broken granite jelly in lime mortar 1 : 8 laid in layers of not more than 6" with tamping, etc., complete	C.ft.	0 3 6	1,258	275
3	Do in clay for foundation with through bonds every 6' apart		0 3 6	1,707	373
4	Sizing under clay for basement with through bonds every 6' apart		0 4 0	678	219
5	Burnt brick in clay for superstructure		0 2 6	3,386	532
6	Burnt brick in lime mortar for superstructure		0 4 0	363	91
7	(a) Burnt stone slabs 6" thick roughly dressed all faces and fixed in mortar bed	S.ft.	0 6 0	107	40
	(b) Burnt stone slabs 4" thick neatly dressed for joints		0 7 0	160	70
8	Cement concrete slabs 1 : 2 : 4 bond slabs and sills, etc.	C.ft.	0 12 0	87	65
9	Plastering with chunam mortar smooth including rounding of corners, etc., complete	Sqr.	3 0 0	57·67	173
10	Wire cut brick in cement mortar 1 : 3 for pillars, with base and capital including cement plastering smooth as per required design	C.ft.	0 12 0	43	32
11	Roofing with brick in cement mortar on precast reinforced cement concrete joists and brick nogging with layers of flat tiles, etc., complete as per standard specifications including plastering top and bottom	Sqr.	55 0 0	17·17	944
12	Providing and fixing reinforced cement concrete chajja 3" to 6" thick with necessary reinforcement and anchorage into wall 12" thick plastering with proof course, etc., complete	S.ft.	0 12 0	830	623
13	Parapet wall with burnt brick in lime mortar 9" thick 3' high including plastering top and bottom, mouldings, rounding offsets base course, etc.	R.ft.	0 10 0	263	164
14	Scaffolding work all round	,,	0 3 0	263	49
15	(a) Flooring with cement concrete 2½" thick over 6" chunam concrete and cement plastering, etc., complete	Sqr.	20 0 0	7·58	152
	(b) Do with hard wearing green cement tiles of approved pattern on concrete bed and pointing, etc., complete	,,	55 0 0	6·64	365
	(c) Do with burnt stone slabs 3" thick two line dressed on concrete bed, 3" thick with cement pointing, etc., complete	,,	40 0 0	3·10	124
	(d) Do with burnt stone slabs 18" Sqr. 3 line dressed on 3" concrete bed including cement pointing, etc., complete	,,	60 0 0	3·10	181
16	(a) Teak wood doors of frames 4"×5" without bottom sills with fly proof shutters with brass hinges, hooks, bolts, etc., complete	S.ft.	1 6 0	73	100
	(b) Do with panelled shutters with brass fittings, etc., complete	,,	1 8 0	154	231
17	Providing and fixing teak wood windows with frames 3"×4" with fly proof shutters, iron fittings, etc., complete	,,	1 4 0	313	391
18	Providing and fixing cement perforated ventilators with wire gauge fixed, etc., complete	,,	1 4 0	45	56
19	Teak wood wall shelves with 3"×4" frames and panelled shutters 4 compartment one inch thick cross planks including brass fixtures, etc., complete	,,	1 8 0	105	158

Sl. No.	Items of work	Unit	Rate	Quantity	[illegible]
			Rs. a. p.		Rs.
20	Laboratory green painting to doors and windows, etc., two coats	Sqr.	1 0 0	7.81	7
21	Wax polishing two coats	,,	7 0 0	3.35	2
22	Cement pointing to basement for racking joints and neatly finishing with lines complete ..	,,	5 8 0	3.20	1
23	White and colour washing two coats	,,	0 5 0	57.57	1
24	Cement asbestos rectangular rain water spouts of 2"×4" including fixing embedded in wall, etc., complete	R.ft.	1 0 0	48	4
25	Providing earthware sinks with cement plastering and galvanised iron outlet pipes, etc., complete	Each	5 0 0	6	3
26	Providing steel racks 6'×4½'×1½' deep 5 compartments as per required design	,,	100 0 0	3	3
27	Providing meat safe with fly-proof shutters, etc., complete as per required design	,,	25 0 0	1	25
28	Preparation tables 6'×4' with marble top ..	,,	30 0 0	3	90
29	Providing chimney arrangements with smoke escaping pipe, etc., complete	,,	1 0 0	3	3
30	Providing preparation table 6'×4' with wooden top, etc., complete	,,	15 0 0	3	45
31	Providing charcoal stove as per approved design adopted for special ward in Krishnarajendra Hospital, ¼" double plate with opening shutters in front, etc.	,,	7 0 0	11	77
32	Providing and fixing collapsible iron gate as per approved design	S.ft.	1 12 0	36	3
33	Providing expanded metal partition wall in store room with a doorway	,,	1 8 0	35	48
	Total ..		..	..	7,151

M. N. LAKSHMANA RAO
Assistant Engineer.

LOWER CHANNELS DIVISION, MYSORE

Notification dated 27th July 1939.

It is hereby notified for general information that unserviceable Tools and Plant and [illegible] mentioned in the enclosed statement will be sold by public auction by the Assistant Engineer, [illegible] Channels Sub-Division, or by any officer deputed by him for the purpose and the place at which, [illegible] they will be auctioned are also noted in the statement subject to the following conditions:—

1. The articles will be knocked down to the highest bidder;
2. The successful bidder should pay the full purchase money on the spot in cash; and
3. If the successful bidder fails to fulfil the above conditions, the articles will be put to auction again and if the realisations thereof fall short of the [illegible] amount originally realised on the conditions of the original bidder shall have to make good the loss to Government by way of compensation.

List of unserviceable articles to be auctioned in different stations attached to No. II Channels Sub Division, French Rocks, on the dates and times noted against each. (Tools and plant surplus articles).

Sl. No.	Names of articles	To be sold [illegible]						Total
		French-Rocks Sub-Division Office at 5 P.M., 15 September 1939		At Bangalore Traveller's Bungalow at 5 P.M., on 9th September 1939		At Yelandur Munsiff's Court at 5 P.M., on 30th September 1939		
	I. Survey and Mathematical Instruments.	Quantity		Quantity		Quantity		
1	Metallic tape 50' ..	No.	2	No.	2	No.	[illegible]	[illegible]
2	Levelling staves 14' ..	,,	..	,,	4	,,	[illegible]	[illegible]
3	Vulcanite Set Square 60° ..	,,	..	,,	..	,,	1	1
4	Foot-rule 4 fold 2'	,,	3	,,	1	,,	..	4
5	Spare scale with offset pieces ..	,,	1	,,	1	,,	..	2
6	Refills 50 ft.	,,	11	,,	..	,,	1	[illegible]

Sl. No.	Names of articles	To be sold in auction at			Total
		French Rocks Sub-Division Office at 5 P.M., 15 September 1939	At Bannur Travellers' Bungalow at 5 P.M., on 9th September 1939	At Talakad Musafirkhana at 5 P.M., on 20th September 1939	
		Quantity	Quantity	Quantity	
	II. Office Furniture.				
1	Office clock	No. 1	No. ..	No. ..	1
2	Badges and Belt	„ 1	„ 3	„ ..	4
3	Lanterns	„ 2	„ 8	„ 1	11
4	G. I. Lock 11"	„ 1	„ 3	„ ..	4
5	G. I. Lock 2"	„ 4	„ ..	„ ..	4
6	Nickle plated lock	..	„ 1	„ ..	1
	III. Inspection Lodge materials.				
1	Brass tumblers	..	„ 6	„ ..	6
	IV. Tools and Plant.				
1	Felling axes	„ 1	„ 1	....	2
2	Pick-axes	..	„ 7	„ 7	14
3	Bill hooks	..	„ 6	„ 3	9
4	Mamties	„ 2	„ 7	„ 10	19
5	Spanners for bidigandies ..	..	„ 8	..	8
6	Bidigandy planks	„ 44	..	..	44
7	Nippers	„ 2	..	..	2
	V. Surplus articles.				
1	Steel punches	„ 2	..	..	2
2	Bends 3 × 4 inches	„ 3	..	..	3
3	Reducer 4 × 3 inches ..	„ 1	..	..	1
4	Flanges of 3"	„ 2	..	..	2
5	C. I. Pipe 5" × 9'	„ 1	..	..	1
6	Gear box for regulator	„ ..	No. 2	..	2
7	Jungle wood planks (doors) ..	..	S.ft. 25	..	25
8	Do (window frame) ..	..	„ 4	..	4
9	Damaged planks of the head sluices	..	„ 15	..	15

D. KRISHNA RAO,
Executive Engineer.

MANDYA DIVISION.

Notification dated 27th July 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 NOON on 21st August 1939, for restoring Bavinahally Tank, Reg. No. 166 of Krishnarajpet Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mandya Division, should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for restoring Bavinahally Tank". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Deposit of Rs. 210 (in words) Rupees Two hundred paid to the Treasury to the credit of "17-(a) Deposits" against the account of the Executive Engineer, Mandya Division. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry anyinterest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 21st August 1939 at Mandya Division. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931). And also furnish a security deposite of Rs. 210 in addition to earnest money.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.